TAG NO.	605-E-105	
SERVICE	INLET SEPARATOR PRE-HEATER	
TYPE/SURFACE	BEM/	FT2
HEAT DUTY	6.2	MM BTU/HR
	SHELL	TUBE
DESIGN PRESS.	800 PSIG	800 PSIG
DESIGN TEMP.	170 ° F	170 ° F
RE-CERTIFIED DESIGN PRESS.	500 PSIG	350 PSIG
RE-CERTIFIED DESIGN TEMP.	300 ° F	300 ° F
INSULATION	H50 MM	H50 MM
MATERIAL	CS+CA 3MM	SS 316L

NOTES

1. PROVIDE STRAIGHT LENGTH AS PER ISO 5167
2. THIS HEAT EXCHANGER IS EX 610-E-107A
3. DELETED
4. DELETED
5. PSV'S PROVIDED TO SPECIFICALLY PROTECT HEAT EXCHANGER IF ISOLATED UNDER PRESSURE.
6. 605-TV-137 A AND B ARE REVERSE ACTING.
7. WORK SHOWN ON THIS P&ID COVERED UNDER MOC-08-0127.

SET @350 Psig 1D2 (FIRE) 605 PSV 139 — NOTE 5 — 3"x2" 3" LO — 2"x1" 3/4" — ASA BDA — 2" LC — 3/4" — 2" LO — 2" LC — ASA BDA — 605-3"-RH-ASA-071 → RH 695-082-01

605-2"-GR-BDA-137-H40 — FREE DRAINING

NOTE 6 SET @ 80 F — 605 TIC 137 H/L — 605 TT 137 RTD — 1-1/2"

605 PG 131 — 3/4"

TO INLET SEPARATOR 605-V-202 ← 605-007-01 — 605-8"-GR-BDA-024-H50

RH 695-082-01 ← 605-3"-RH-ASA-070

SET @500 Psig 2J3 (FIRE) PILOT — 605 PSV 138 — NOTE 5 — 3" LO — 3/4" — ASA BCB — 2" LC — 3/4" — 2" LC — ASA BCB — 3/4" — LO 2"

605 FI 135 — 605 FT 135 — NOTE 1 — 605 FE 135

605 PG 135 — 3/4"

605 TG 135 — 1-1/2"

FROM DE-ETHANIZER BOTTOM OUTLET LINE — 655-005-01 — 655-8"-GT-BCB-040-H50

605-2"-GT-BCB-135-H40 — FREE DRAINING

605-2"-RH-ASA-072

605 TYC 137B — 605 TV 137B — 8" 8"x4" 8"x4" LOW POINT 8" — 4" FO — 3/4" 3/4" — 4" — H50 P40

2"-600# — 20"x8" — 20"x8" — 300#RF 600#RF

605-E-105 — NOTE 2

600#RF 300#RF — 20"x8" 20"x8" — 2"-600#

605 TYC 137A

605 PG 138 — 3/4" — 605 TG 138 — 1-1/2"

605 TV 137A — 8" 8"x4" 8"x4" 8" — 4" FC — 3/4" 3/4" — 4" — LOW POINT

ASA BDA

TO NGL RUNDOWN COOLER 655-E-107 ← 655-005-01 — 655-8"-GT-BCB-041-P40

2" 2" — 605-2"-GR-BDA-130

655-2"-GT-BCB-XXX

2" 2" — BCB BDA

FROM 605-PIC-130 — 605-007-01 — 605 PDI 137 H=15 PSI — 605 PI 137

605 PT 137 — 3/4"

605 TG 136 — 1-1/2"

FROM SLUG CATCHER — 605-007-01 — 605-8"-GR-BDA-023 — LOW POINT

2" 2" — 605-2"-GR-BDA-131 — 3/4"

BCD3-000-42-PID-1-001-01 TO 012	P&ID SYMBOLS

NO.	REFERENCE DOCUMENT

REV.	ISSUED	PURPOSE	LDE	PEW	PW	STATUS	DATE
COMPANY STATUS							
4		AS BUILT	21-MAR-12				
3		RE-ISSUED FOR CONSTRUCTION	10-SEP-09	WD	WD	BG	RSK
2		RE-ISSUED FOR CONSTRUCTION	23-MAR-09	WD	WD	BG	RSK
1		RE-ISSUED FOR CONSTRUCTION	20-MAR-09	WD	WD	BG	RSK
0		FOR CONSTRUCTION	12-MAR-09	WD	WD	BG	RSK
A		FOR REVIEW	04-MAR-09	WST	WD	BG	
NO.		DESCRIPTION	DATE	BY	CHKD	RVD	APVD

CONTRACTOR REVISIONS

PT. CHIYODA INTERNATIONAL INDONESIA — PT. Sempec Indonesia

CONTRACT	JOB	E3X01

PetroChina International Jabung Ltd.

BETARA COMPLEX DEVELOPMENT

PIPING AND INSTRUMENTATION DIAGRAM
BETARA GAS PLANT
INLET SEPARATOR PRE-HEATER

SCALE : NTS

DOCUMENT	REVISION
BCD3-605-42-PID-1-008-01	4

FILE NAME :\BCD3-605-42-PID-1-007-01.DWG